Pegler Yorkshire GB00049 HIU Test: VWART Calculation

April 2016

1 Introduction

The Pegler Yorkshire GB00049 HIU was tested according to FairHeat's "*Modified Swedish Test UK HIU Test Regime V1-Rev-010"* by SP Swedish Technical Institute during January 2016.

This document sets out the calculated Volume Weighted Return Temperatures (VWART) for the Pegler Yorkshire GB00049 and should be considered a companion document to the "*5P07886C-rev2 - Pegler Yorkshire (Meibes) 160415"* document produced by SP Swedish Technical Institute, which is published at www.sp.se and www.fairheat.com.

The methodology for calculating the different Volume Weighted Return Temperature metrics is set out in the "*Modified Swedish Test UK HIU Test Regime V1-Rev-010"* document.

In order to assess overall performance of HIUs tested according to the UK HIU Test Regime Technical Specification published by FairHeat, a number of derived results were calculated from the output from the tests, assuming 'standard' UK operating conditions of:

- 75°C primary flow temperature
- 55°C Domestic Hot Water (DHW) set point
- 70°C/40°C space heating flow and return temperatures
- Standby/Keep-hot function operational and continuous
- 0.5 bar differential pressure across the HIU

2 Volume Weighted Average Return Temperature Performance

The table below sets out the VWART metrics for the Pegler Yorkshire GB00049.

VWART Calculation	Nomenclature	VWART (°C)	Volume(m^3 pa)
DHW	$VWART_{DHW}$	37.2	37.3
Space Heating	$VWART_{SH}$	50.2	56.3
Standby / Keep-hot	$VWART_{SBY}$	47.7	74.0
Heating Period (including space heating)	$VWART_{HEAT}$	49.4	64.4
Non-Heating Period (not including space heating)	$VWART_{NONHEAT}$	44.2	103.2
Overall	$VWART_{HIU}$	**44.6**	**167.5**

3 Observations

The HIU met all of the testing requirement parameters as set out in FairHeat's "*Modified Swedish Test UK HIU Test Regime V1-Rev-010".*

4 Disclaimer

While the Swedish District Heating Association's Technical Regulations, F:103-7e, have been produced with the purpose of certifying district heating substations as 'fit for purpose' prior to connection to district heating

systems, the test regime set out within the technical specification is **not** for use for certification and in no way are the results to be interpreted as "certifying" or "not certifying" HIUs as being fit for connection to Heat Networks in the UK (or elsewhere).



This work is licensed under a Creative Commons Attribution-NonCommercial-NoDerivs 3.0 Unported License. To view a copy of the license, visit: http://creativecommons.org/licenses/by-nc-nd/3.0/